

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>28</u> N. <u>5</u> W. <u>•</u>	C-8
2. PROPERTY CONTROLLING IN SECTION <u>20</u>	T. <u>28</u> N. <u>5</u> W. <u>•</u>	12
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on JANUARY 11, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-8 DEPT MONUMENT (KJO-1969); PER B.L. CAUKINS POST BOTTOM AND B.T. STUMP'S, NOV. 1919. CAUKINS USED THIS CORNER TO SUBDIVIDE SECTION 20.
- 12 FOUND 1/2" X 16" THREADED ROD IN ROTTED POST BOTTOM REMAINS, FOR S 1/8 CORNER ON N-S 1/4 LINE IN SECTION 20 (SW CORNER OF GOV'T. LOT 4); FITS MAY 1920 B.L. CAUKINS' B.T.'S, SUG. 12" (NOW 16" FACE STILL SHOWS), S58° (B.L.C. BOOKED S58°E IN ERROR), 46.5' AND FOUND DEFINATE TREE HOLE, S21-1/2°E, 15.8'±. SEE CAUKINS FIELD NOTE (PG 40) AT ANTRIM COUNTY ROAD COMMISSION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>C-8</u>	<u>12</u>
FD DNR MON. - ADDED CEDAR POST,	FD 1/2" THREADED ROD; REPLACED W/5/8"
*16" MAPLE S74°E 44.9	X 36" RE-ROD W/RLS CAP & SET CEDAR POST
13" TW. MAPLE N20°E 54.4	W/LOC TAG
3" CHERRY S73°W 39.4	5" MAPLE N72°W 5.9
	*16" MAPLE S58°W 46.5
	5" IRONWOOD S32°E 15.0
	FD 1/2" RE-ROD S04°14'W 8.39

* = CAUKINS B.T.

SIGNED BY Carl F. Roser 05-02-83 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. #12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

BLUE LAKE Twp.
KALKASKA COUNTY

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET