

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>28</u> N. <u>●</u> , R. <u>5</u> W. <u>●</u>	K-3; L-5; L-7; M-5
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Corey J. Hughes, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 9, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration:~~

C. (continued)

M-5  
Set DNR mon. & cedar post  
18" W. Pine Stmp. N66°E 57.3  
30" W. Pine Stmp. N36°E 13.67  
36" W. Pine Stmp. S56°W 40.75  
E-W Trail approx. 220' North

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- 3 Found pipe in concrete set by Marcus Schaaf, RLS, app. 1946, by original B.T. sites. Replaced with DNR monument.
  - 5 Set DNR monument M.O.L. as per B.L.M. instructions.
  - 7 Fd. pipe in concrete set by Schaaf, RLS, from original B.T. sites. Replaced with DNR monument. Fd. original line tree to East which seems to verify this corner.
  - 5 Fd. pipe in concrete set by Marcus Schaaf, RLS, approximately 1946 by original B.T. sites. Replaced with DNR monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


K-3	L-5	L-7
DNR monument & cedar post	Set DNR mon. & cedar post	Set DNR monument & cedar post
12" R. Pine N01°E 15.1	30" Maple Clmp. S18°W 24.6	10" W. Pine N31°W 68.5
9" Maple S82°W 20.6	24" Trpl. Maple N52°W 27.9	4" Spruce N82°W 15.6
10" R. Pine N46°W 22.4	14" W. Pine S87°E 12.1	12" W. Pine S08°W 88.0
S. edge of pine plantation	N-S Cycle Trail 66' West	Enter Swamp 55' East
15' North	E-W R/L 0.76' South	
E-W R/L 7' North		

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:  
Above corners by Corey J. Hughes, R.L.S. #20706; Title X  
Survey for Mich. D.N.R., Summer, 1976.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
APPROVED AND SIGNED BY Carl F. Roser 1-12-78 DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

BLUE LAKE TOWNSHIP  
KALKASKA COUNTY