

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>28</u> N. <u>•</u> , R. <u>5</u> W. <u>•</u>	<u>A-9; A-10; A-11</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____, R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Nov. 29, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-9 Found & accepted 2" pipe (buried below B. Top surfaced road) in approx. rd. intersection (NNE-SSW-E), said pipe being in line with old fence to west. Corner fits B.L. Caukins survey of Sec. 25, T28N-R6W, dated 1919.
 - A-10 Recovered Conc. Mon. with bronze cap. Dept. RLS, Greg Shadko, P.A.S. #40-3, dated 1943. Greg Fd. B.L. Caukins stake from Caukins survey of 1919.
 - A-11 Recovered 1 1/4" pipe as fd. & accepted by R.L.S. J. Wilcox; also fits W.S. Merrill survey dated Jan. 1922. Cor. falls in Newer E-W Power line opening; 2.5' Westerly of cor. fence post (Fns N70°E & S06°E)
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9	A-10	A-11
Found 2" pipe raised W/1"X9" pin W/1 1/4" top.	Found Shadko Conc. Mon. with Bronze Cap. & set Ced. post	Found 1 1/4" Pipe & added ced. post w/loc. tag
14" Maple N56°W 34.19	14" Maple N17°W 77.6	P.Pole#58 S82°E 41.18
8" R.Pine N13°W 57.90	9" Twin Maple N65°W 18.1	8" Maple S18°W 33.43
P.Pole N65°E 51.30	9" Maple S12°W 30.2	9" Maple N20°E 61.56
Set Ced. Post w/Loc.Tag S45°E 47.0		8" Maple N22°W 78.22


SIGNED BY Carl F. Roser DATE 3-31-76

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

BLUE LAKE TOWNSHIP
KALKASKA COUNTY