

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>28</u> N. <u>5</u> R. <u>W.</u>	<u>A-12; C-11; C-12</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION <u>31</u>	T. <u>28</u> N. <u>5</u> R. <u>W.</u>	<u>* on line between C-12 & c-13; 661.12'-N of C-13</u>
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Dec. 2, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on Nov. 28, 1977, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~--- A --- Description of original monument and accessories and/or subsequent restoration ---~~
 C. (continued)

*
 Drove 1 1/4"X18" Iron Rod in ctr. N-S gravel rd.
 5" Maple N82°E 30.4
 14" Maple N80°W 41.0
 10" Maple S73°W 68.9
 Set ced. post w/loc. tag
 Due W 33.0

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-12 Fd. 1/2" re-rod (in swp.) with RLS cap (J.Wilcox #14102) as re-established mid-way & on line between fd. Sec. Cor's. to N. & S. This fits W.S. Merrill survey dated Jan. 1922; F.B.#33, Pages 105-107.
- C-11 Re-estb. NE Cor. S-31 per W.S.Merrill Sur., dated Jan. 1922. Set Cor. at pro-rated distance to W.S.M. between fd. SE & E 1/4 Cor. & in ctr. N-S dirt rd. which fits W.S.M. dist. on N. line Sec. 31 & 32 and U.S. dist. on N. line of Sec's 32 & 33. Ctn. of E-W Power line is 1'+ South.
- C-12 Fd. 1 1/4"X16" Iron which fits W.S. Merrill survey dated Jan. 1922. Cor. is in approx. ctr. of N-S gravel road.

* C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

A-12	C-11	C-12
Fd. 1/2" re-rod & added	Drove 1 1/4"X18" Iron rod	Fd. 1 1/4" Iron & drove 1 1/2"X22"
DNR Mon. & ced. post	12" Maple S28°W 82.4	pipe around same
15" W.Pine S62°W 109.0	P.Pole N86°W 89.26	10" Maple N59°E 43.7
3" Twin cedar S85°E 11.26	12" Maple N29°W 81.0	9" Maple S82°E 36.1
3" Cedar N09°E 18.55	7" Maple S12°E 109.5	10" Maple S67°W 68.2
N-S gravel rd. Due W 115'+	Set ced. post w/loc. tag N85°W 40.0	Set ced. post w/loc. tag Due W. 33.0
	Ctr. N-S gravel rd. Due E 4'+	

SIGNED BY _____

Carl F. Roser

DATE 3-31-78

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____


CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____

MICHIGAN REGISTERED LAND SURVEYOR

DATE _____



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

BLUE LAKE TOWNSHIP
KALKASKA COUNTY