

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:				CORNER CODE NUMBER
	T.	N. S.,	R.	E. W.	
1. PUBLIC LAND SURVEY _____					
31	28			5	14
2. PROPERTY CONTROLLING IN SECTION _____	T.	N. S.,	R.	E. W.	
32	28	●		5	3
3. MISCELLANEOUS PROPERTY IN SECTION _____	T.	N. S.,	R.	E. W.	
31	28	●		5	*on line between C-11 & C-12; 663.42-S. of C-11
4. LOT NO. _____, RECORDED PLAT _____					
5. PRIVATE CLAIMS _____					

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Nov. 28, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on Nov. 28, 1977, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 14 Set 1/8 Cor. midway & on line between fd. 1/4 Cor. to N. & Sec. Cor. to S.
- 3 Set 1/8 Cor midway & on line between fd. 1/4 Cor. to S. & Establish Sec. Cor. to N.
- \* Establish SE Cor. of NE1/4 - NE 1/4 - NE 1/4 of S-31 per Std. B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

14	3	*
Drove 1 1/4" X 18" Iron Rod	Drove 1 1/4" X 18" Iron Rod	Drove 1 1/4" X 18" Iron Rod
12" Maple S40°E 41.5	in ctr. N-S gravel rd.	8" Maple S56°W 29.32
6" Maple S72°W 75.8	12" Maple N64°E 49.42	8" Maple N73°W 27.64
8" Tw. Maple N62°W 59.4	8" Maple S62°E 64.40	12" Maple N54°E 65.95
Set ced. post w/loc. tag	9" Maple S47°E 37.21	Ctr. N-S gravel Rd.
Due W 33.0	Set ced. w/loc. tag	Due E 8'+
Ctr. N-S gravel rd.	Due E 33.0	Set Ced. post w/Loc. tag
Due W 2.5		Due W 16.5

SIGNED BY Carl F. Roser

DATE 3-31-76

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_

DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_

DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

BLUE LAKE TOWNSHIP  
KALKASKA COUNTY