

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>28</u> N. <u>5</u> W. <u>5</u>		<u>L-1; L-3; M-1; M-3</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, N. _____, S. _____, R. _____, E. _____, W. _____		_____
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, N. _____, S. _____, R. _____, E. _____, W. _____		_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Corey J. Hughes, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 5, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- L-1 Set DNR monument M.O.L. as per B.L.M. instructions. (¼ Cor. Comm. to Sec. 36 (29-5) & Sec. 1 (28-5)).
 - L-3 Set DNR monument M.O.L. as per B.L.M. instructions.
 - M-1 Cor. Comm. to T28 & 29N-R4 & 5W. Fd. pipe in concrete set by Marcus Schaaf in 1946 from original B.T.'s. Also fd. a DNR monument out of ground. Replaced with new DNR monument & re-witnessed. USBT Stub as fd. by M. Schaaf now tipped-over with evidence of having been refaced & rescribed, is S13°E 12.5'; which fits U.S. tie.
 - M-3 Fd. pipe in concrete set by Marcus Schaaf, RLS approximately 1946 by sites of original B.T.'s. Replaced with DNR monument. Fd. Schaaf's 24" Tam. stp., S10°W, 28.4'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	L-1	L-3	M-1	M-3
8" Maple	N50°E 8.9'	Set DNR mon. & ced.post	Set DNR mon. & Ced.post	Set DNR mon. & ced.Post
6" Maple	S13°E 44.7'	12" Maple N69°E 6.5	4" Balsam S65°W 9.1	12" Balsam N86°E 8.6
11" Maple	S30°W 36.1'	18" Twn. Maple	3" Balsam N83°E 66.1	13" Balsam S25°E 12.4
9" Twn. Maple	S84°W 41.4'	S65°E 53.2	8" Balsam S03°E 45.1	10" Balsam N65°W 21.9
E-W Rand Due S.	8'	10" Maple N88°W 56.2	R/L West 11.5' South	
		E-W R/L 37.25' North	Schaaf's 24"x7" W.P.	
		RR GRade app. 775' West	stub, S18°E 23.1	

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:
Above corners by Corey J. Hughes, R.L.S. #20706; Title X Survey for Mich. D.N.R., Summer 1976.

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Carl F. Roser 1-16-78 DATE _____
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

KALDASKA COUNTY
BLUE LAKE TOWNSHIP