

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>28</u> N. <u>5</u> W. <u>5</u>	<u>I-6; J-6</u>
2. PROPERTY CONTROLLING IN SECTION <u>14</u>	T. <u>28</u> N. <u>5</u> W. <u>5</u>	<u>8; 9</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Corey J. Hughes, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 4, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories found and/or subsequent restoration~~

C. (continued)

9

Set 3/8"x1/2"x30" iron & Cedar post w/Loc Tag
 10" R. Pine N75°W 7.5
 5" W. Pine S47°E 20.7
 10" R. Pine S72°E 37.0
 E-W R/L 1.5' North

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-6 Replaced 1/2" iron by RLS C. E. Ostling with DNR monument. Ostling set iron M.O.L.
- J-6 Set DNR monument at intersection of 1/4 lines.
- 8 Set corner M.O.L. between 1/4 Cor. W. & Ctr. Sec. E.
- 9 Set corner M.O.L. between 1/4 Cor. E. & Ctr. Sec. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6	J-6	8
Set DNR mon. & cedar post	Set DNR mon. & cedar post	Set 3/8"x1/2"x30" iron & cedar post w/Loc Tag
Fd. 12" Maple in clump of 4	14" Maple Clmp. N15°E 29.4	Twn. 14" Maple S33°W 20.8
S80°E 33.0	12" Maple Clmp. S31°W 47.6	10" Maple N22°W 7.1
Fd. 7" Maple in clump of 7	14" Maple Clmp. S52°W 61.7	5" Twn. Maple N29°E 19.4
N72°W 59.9	N-S Road 215'± East	E-W R/L is 3.0' North
R/L West 3.6' North		N-S Trail Road 56.6' West
R/L N-S 15' West		
2" Maple		
S15°W 32.2		

SIGNED BY _____ DATE _____


SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

Above corners by Corey J. Hughes, R.L.S. #20706; Title X Survey for _____, Summer 1976.

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Carl F. Roser 1-16-78 DATE _____
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

BLUE LAKE TOWNSHIP
KALKASKA COUNTY