

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>28</u> N. <u>5</u> R. <u>5</u> W.	<u>I-7; J-7</u>
2. PROPERTY CONTROLLING IN SECTION <u>14</u>	T. <u>28</u> N. <u>5</u> R. <u>5</u> W.	<u>15; 16</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Corey J. Hughes, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 30, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration~~  
C. (continued)

- 16
- |   |       |       |
|---|-------|-------|
| Set 3/8"x1/2"x60" iron rod & cedar post w/Loc Tag |       |       |
| 5" Beech  | N70°E | 9.5   |
| 4" Maple In Clump                                 | S17°W | 20.6  |
| Maple Clump                                       | N46°W | 32.3  |
| E-W R/L   | 1.68' | North |

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-7 Fd. Sq. Concrete monument (by W. S. Merrill-1927) that fits "North Blue Lake" and "Blue Lake" plats. Monument had been disturbed - replaced w/DNR monument.
- J-7 Set DNR monument M.O.L. per B.L.M. instructions.
- 15 Set 1/16 Cor. M.O.L. between Sec Corner W & 1/4 Corner E.
- 16 Set 1/16 Cor. M.O.L. between 1/4 Corner W & Sec Corner E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7	J-7	15
Set DNR mon. & cedar post	Set DNR mon. & cedar post	Set 1/2"x3/8"x60" iron rod & ced.post
Fd. 7" Beech S02°W 25.3	12" Elm S03 E 49.7	W/Loc Tag
Fd. 5" Maple S76°E 17.9	10" Tw. Cherry	8" Tw. Maple N18°E 14.1
Fd. 8" Beech N10°E 28.8	N07°E 38.5	8" Tw. Maple S61°E 16.8
Trail Rd. N-S 119' East	8" Aspen N40°W 24.3	6" Maple S08°W 24.2
Mon. on Horse Trail N-S	10" Cherry S87°E 75.4	E N-S Trail 33.4' East
Fd. Sq. Conc. Mon.	Trail Rd. N-S, 48' West	E-W R/L 5.06' North
South 360.0'	E-W R/L 3.4' North	
Fd. Round Conc. mon.		
SIGNED BY North 32.7'		

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_


FOR STATE AND UNITED STATES AGENCIES:

Above corners by Corey J. Hughes, R.L.S. #20706; Title X Survey of 12028 Blk. 12028 R. 12028 Summer, 1976

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Carl F. Roser 1-16-78 DATE \_\_\_\_\_  
BRIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Carl F. Roser



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

BLUE LAKE TOWNSHIP  
KALKASKA COUNTY