

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>28</u> N. <u>8.</u> , R. <u>5</u> W.	<u>I-5</u> , <u>M-4</u> , <u>M-6</u> , <u>M-7</u>
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 6, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration:~~  
**C. (continued)** M-7

Fd. DNR Mon., (Schaaf Mon. on ground)  
 & ced. post  
 26" W. Pine Stp. S01°E 30.7'  
 18" W. Pine Stp. S79°W 33.2'  
 12" W. Pine S70°E 31.70'  
 3" Maple S18°W 42.90'  
 N-S gas line Due E. 210'±

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
**I-5 Recovered Dept. Mon. from previous Dept Survey(1968); said Mon. being a perpetuation of B. L. Caukins Corner dated 1919. Cor. is on random line East, West, & North**

**M-4 Set DNR Mon. equidistant on line & between fd. Sec. Cor's, to North & South.**  
**M-6 Set DNR Mon. equidistant & on line between Sec. Cor's, to N & S. Note: In 1951, the Dept. re-monumented M. Schaaf Mon. which was later found to be incorrect. We removed the Dept. Mon., whose position would be N06°43'E, 346.78' from above estab. Cor. by S.P.**  
**M-7 Fd. & accepted D.N.R. Mon. as set in previous Dept. Survey of 1951 which perpetuated Marcus Schaaf Cor.**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-5	M-4	M-6
Fd. Dept. Mon. & added ced.post	Set D.N.R. Mon. & Ced.post	Set DNR Mon. & ced.post
12" Maple Clump N13°W 90.0'	12" Maple S24°E 138.1'	3" Pin Cherry N10°E 71.49'
12" Twin Beech S39°W 92.5'	21" W. Pine N55°W 82.8'	27" Pine Stp. S25°E 64.9'
3" Cherry S21°E 44.6'	10" Maple N54°E 99.7'	22" Pine stp. remains
	30" Pine Stp. N89°W 37.0'	S82°W 39.4'
	N-S sand rd. Due W. 435'±	N-S Gas line East 370'±

SIGNED BY Carl F. Roser 2-5-78 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

BLUE LAKE TOWNSHIP  
KALKASKA COUNTY

