

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>28</u> N. <u>•</u> , R. <u>5</u> W. <u>•</u>	K-6, <u>(G-6)</u>
2. PROPERTY CONTROLLING IN SECTION <u>14</u>	, T. <u>28</u> N. <u>•</u> , R. <u>5</u> W. <u>•</u>	<u>10</u>
3. MISCELLANEOUS PROPERTY IN SECTION <u>14</u>	, T. <u>28</u> N. <u>•</u> , R. <u>5</u> W. <u>•</u>	<u>*Cor. is 1/2 way & on line Btw. K-7 & S-14, #14.</u>
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 2, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on October 10, 1977, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration.~~

C. (continued)

*
Set 1/2"x3/8"x48" Iron & ced, post
W/Loc. Tag.
10" Maple N46°E 22.5'
6" Maple N27°W 19.1'
6" Maple S48°E 11.0'
on N-S Random line

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
10 Fd. Conc. Mon. for 1/8 corner as established in Dec, 1946; NE Corner of "North Blue Lake" Sub'n., Sec. 15, T28N-R5W.

K-6 Re-establish 1/2 Cor. equidistant & on line between fd, M. Schaaf Sec. Cor's. to N & S.

G-6 Recovered Dept. Mon. as established in previous Dept. Survey (1968) by proportionate measure.

* Established SE Cor. of N1/2-SE1/4-SE1/4, Sec. 14 per Std, B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

10	K-6	G-6
Fd. Conc. Mon	Set D.N.R. Mon. & ced, post	Fd, Dept. Mon. & Set ced, post
Set ced, post W/Loc. Tag	12" Maple S34°E 21.1'	14" Maple N40°W 22.1'
14" W. Pine S70°W 31.3'	11" Maple S65°W 17.3'	10" Triple Beech
12" Maple in Clp. S14°W 61.5'	10" Twin Maple N34°E 20.4'	S10°E 28.4'
9" W. Pine N68°E 72.4'	N-S Rand. is 1'± East	6" Maple S63°E 27.8'
	Rand. W. is 1'± North	N-S Rand. Due E 16'
		Ctr. of gas line opening
		Due S 155'±


SIGNED BY Carl F. Roser 2-5-78 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

BLUE LAKE
KALKASKA

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTR. REV

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET