

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>28</u> N. <u>•</u> , R. <u>5</u> W. <u>•</u>	<u>G-7</u> , <u>H-9</u> , <u>I-9</u> , J-9
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 11, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

J-9

~~A. Description of original monument and accessories and/or subsequent restoration:~~

C. (continued) **Fd. Conc. Mon. & set cedar post**  
W/Loc. Tag.

4" Maple	N79°E	24.9'
4" Maple	S26°W	20.5'
8" Maple	S85°W	34.4'

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- G-7 Recovered Dept. Mon. from previous Dept. Survey (1968); said corner being a perpetuation of B.L. Caukins corner dated 1919.
  - H-9 Recovered Dept. Mon. from previous Dept. Survey (1968); said corner being a perpetuation of B.L. Caukins Cor. (1919) & used by other Local Surveyors.
  - I-9 Recovered Dept. Mon. from previous Dept. Survey by G. Shadko & accepted by KJ. Ostling in 1969 Dept. Survey, which is believed to perpetuate B.L. Caukins Cor. (1919). Fits U.S. dist. to Lake Better than Schaaf Cor. & was used in subsequent subd. of Sec's. 22&23.
  - J-9 Fd. Conc. Mon. per "Bass Lake Plat". Mon. is within 6' of a 1/4 position by single proportion.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7	H-9	I-9
Fd. Dept. Mon. & Set ced. post	Fd. Dept. Mon. & set ced. post	Fd. Dept. Conc. Mon. w/Brass Cap & set cedar post
8" Maple S87°E 25.6'	5" Beech N20°E 15.2'	8" Maple S10°W 14.8'
8" Twin Beech S09°E 18.2'	9" Maple N11°W 33.08'	8" Twin Maple N73°W 21.6'
12" Maple in clp. N50°W 56.3'	10" Twin Beech N79°W 16.3'	9" Triple Maple S44°E 53.6'
6" Maple N12°E 6.5'	10" Maple S28°W 29.15'	
	N-S gravel rd. Due E 89'	
	Cor. falls on N. edge of old E-W R.R. grade.	Fd. Schaaf Mon. S63°13'E 110.05'
		E-W Trail Due N 21'


SIGNED BY Carl F. Roser 2-5-78 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

BLUE LAKE TOWNSHIP  
KALKASKA COUNTY