

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>28</u> N. <u>•</u> , R. <u>5</u> W. <u>•</u>	H-1, H-3, I-3
2. PROPERTY CONTROLLING IN SECTION <u>3</u>	, T. <u>28</u> N. <u>•</u> , R. <u>5</u> W. <u>•</u>	15
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 3, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration:~~
C. (continued) I-3

Fd. Dept. Mon.; Added Ced. post
 16" Twin Maple N79°W 19.8'
 14" Twin Maple S09°W 56.2'
 9" Maple S55°E 16.4'
 Cor. on random lines N-E-W.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
H-1 Recovered Dept. Mon, established in previous Dept. Survey (1957) as established by proportionate measurement to U.S.

15 Establish 1/8 Cor. equidistant & on line between Sec. Cor, West & 1/4 Corner East.

H-3 Recovered Dept. Mon from previous Dept. Survey (1968), said Corner being a perpetuation of B.L. Caukin's Corner dated 1919.

I-3 Fd. & accepted Dept. Mon. set in previous Dept. survey of 1968, which perpetuated Fd. B.L. Caukin's (1919) post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1	15	H-3
Fd. Dept. Mon & cedar post	Set 5/8"x36" Re-rod	Fd. Dept. Mon & ced. post
W/Loc. Tag.	W/Plastic Cap & ced. post	6" Maple N55°W 39.4'
6" Cherry N76°W 21.88'	W/Loc. Tag	8" Twin Maple N59°E 28.4'
7" Cherry S01°E 19.25'	10" Maple N69°E 37.7'	6" Maple S75°E 20.5'
8" W.Pine S79°W 80.52'	12" Twin Maple S19°E 24.4'	8" Triple Maple S87°W 21.3'
S 1/2 Cor., T29N-R5W (Fd. Dept. Mon.) is S89°31'E, 8.70'	6" Maple S23°W 36.0'	


SIGNED BY Carl F. Roser 2-5-78 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

**BLUE LAKE TOWNSHIP
KALKASKA COUNTY**