

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>28</u> N. <u>•</u> , R. <u>5</u> W. <u>•</u>	G-3; J-1; J-3; K-1
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. _____, R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Corey J. Hughes, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 4, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and recovery and/or subsequent restoration:**

- Set DNR mon. & cedar post
- 5" R. Pine N18°W 27.4
- 10" Cherry S52°W 23.6
- 5" R. Pine S57°W 4.7
- E. edge of pine plantation is 27' West
- E-W R/L 5' South
- 12" Cherry S09°W 29.6

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- G-3 Found DNR mon. set by K.J. Ostling, RLS, as perpetuating a location set in 1919 by B.L.Caulkins, RLS. A. Erickson, field work by T.C. Tuller, Rapid City, Set a ½" rod (in error) in 1954 that is: N49°13'E, 86.9'.
- J-1 Set N½ Cor., S-2, Pro-rated to U.S. & on line between fd. NE S-1 & fd. SW S-35 (T29N-R5W).
- J-3 Set DNR mon. M.O.L. as per B.L.M. instructions.
- K-1 Set DNR mon. for Sec. Cor. to Sec's 35 & 36 (T29N-R5W) & Sec's 1 & 2 (T28N-R5W) Pro-rated to U.S. and on line between fd. NE S-1 & fd. SW S-35 (T29N-R5W).

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-3	J-1	J-3
Fd. DNR mon. in E of road	Set DNR mon. & ced. post	Set DNR mon. & cedar Post
4" R. Pine S40°W 38.8	w/Loc. Tag	8" Maple S87°E 36.4
5" R. Pine S35°E 101.2	18" Cherry N52°W 67.3	6" Maple S22°W 8.8
7" Twn. Maple N52°E 58.5	8" Cherry N67°W 68.6	5" Maple N77°W 38.6
6" Ced. Post 33.0' East	3" R. Pine S66°W 10.0	E-W R/L 3.87' North
	4" R. Pine S03°W 6.7	N-S trail rd. 12.0'E
	14" Cherry S65°E 108.8	
	S½ Cor. S-35	
	T29°N - R5W (DNR mon.)	
	is S89°35'E, 3.3'	

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

**FOR STATE AND UNITED STATES AGENCIES:**


Above corners by Corey J. Hughes, R.L.S. #20706; Title X Survey for Mich. D.N.R., Summer, 1976

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Carl F. Roser 1-16-78 DATE \_\_\_\_\_

**Carl F. Roser**

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

**BLUE LAKE TOWNSHIP  
KALKASKA COUNTY**