

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>9W</u>	<u>B-1</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property In Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 APR 29 AM 8:17
REG. OF DEEDS
W. J. Bond
9705
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-1	1830	GLO	Mullett	Not Set
	1948	Kent Co. Wit.		3/4" Iron
	1974	LCRC #704	Bonnema	"T" Iron
	1977	LCRC #967 & #1036	Ankrom	1/2" Iron
	1996	LCRC #9599	Jonker	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 7/24/96 and was recorded per LCRC #9599

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker on Twp. Line in place of the "T" Iron he found. Said "T" Iron checks with Kent Co. Wit. and LCRC's #704, #967, #1036.

LCRC #9599

Nail & KC Remon. tag E. side 12" Hickory	N32°W	34.72'
Nail & KC Remon. tag W. side 20" Hickory	S05°E	38.06'
PK Nail E. side Power Pole	N59°W	94.39'
Nail & KC Remon. tag W. side 14" Hickory	N45°E	47.61'
Standard Corner - West		85.37'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1 Standard Kent County Monument		
Nail & KC Remon. tag E. side 14" Hickory	N32°W	34.66'
Nail & KC Remon. tag W. side 20" Oak	S05°E	38.06'
PK Nail E. side Power Pole	N59°W	94.39'
Nail & KC Remon. tag NW side 18" Hickory	N45°E	47.25'
Kent Co. Mon. (B-13, T6N, R9W)	West	85.18'



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN Harry Hubert