

**SURVEY & REMONUMENTATION**

MAR 03 1998

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in  
**KENT COUNTY**

(County)

Located In: Corner Code #

1. Public Land Survey	T <u>5</u> N	R <u>9</u> W	B-4
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 OCT 14 AM 10:01  
REG. OF DEEDS  
*David J. [Signature]*

**10019**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on June 16, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

B-4	1830	GLO	Mullett	Not Set
-----		Williams & Works		No information
1977		Consumers Power Co.	Ankrom	Set/Used intersection 1/4 lines
1988		Survey	Roosien	Shows C 1/4 corner on survey
1989		Survey (Exxel)	Herrema	Capped Iron
		30" Oak NE 3.48	5" Red Birch NW 16.50'	
		15" Hickory S 10.10'	18" Tw. Oak SW 30.59	

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

B-4 Found Capped (Roosien) Rerod per the following witnesses:  
 Fd. Nail W. side 36" Oak N35°E 3.52'  
 Fd. Spike NE side 6" Red Birch N45°W 16.59'  
 Fd. Spike W. side 18" Hickory S05°W 10.04'  
 Fd. Spike NW side 24" Tw. Oak S70°W 30.59'  
 Fence to South is 1.5' East & Fence to West is 1' North  
 Capped Rerod is 0.1 N. and 0.1' E. from true intersection of 1/4 lines

The Capped Rerod is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

B-4 Set Kent County Monument (Harrison) in place of the Capped Rerod  
 Nail & KC Remon. W. side 36" Oak N35°E 3.52'  
 Spike NE side 6" Red Birch N45°W 16.59'  
 Spike W. side 18" Hickory S05°W 10.04'  
 Nail & KC Remon. tag NW side 24" Tw. Oak S70°W 30.59'  
 Fence to South is 1.5' East & Fence to West is 1' North



Signed by *Kirk Breitels*  
 Surveyor's Michigan License No. 30077

Date 8/28/97

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 7/24/97  
 CHAIRMAN *[Signature]*