

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T	5N	R	9W	B-8
T		R		
T		R		
T		R		
S		R		
S		R		
S		R		
S		R		

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

REG. OF DEEDS

Handwritten signature

97 NOV 13 PM 1:00

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

10259

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Kirk Breitels, in a field survey on Sept. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- B-8 1830---GLO---Not Set
- Williams & Works---No information
- Kent Co. Wits.---No information
- 1986---Survey---Exxel---Intersection of 1/4 lines

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/25/97
CHAIRMAN Henry Stuber

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B-8 Established Intersection of 1/4 lines - found nothing at that location.
- Location of Intersection of 1/4 lines on remains of N-S fence ±.


Found Iron Pipe 5.0' S. & 2.4' W. - Do not have any information for this.

Measurements using Intersection of 1/4 lines agrees with Exxel survey

The Intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-8 Set Standard Kent Co. Monument (Harrison) at the Intersection of 1/4 lines.
- Nail & KC Remon. tag N. side 16" Oak S80°W 13.26'
- Nail & KC Remon. tag W. side 12" Oak S20°E 45.10'
- Nail & KC Remon. tag NE side 22" Oak S45°E 25.32'
- Nail & KC Remon. tag SE side 22" Oak N45°E 21.22'
- Nail & KC Remon. tag W. side 20" Oak N15°E 46.67'
- 1" Iron Pipe - SSW 5.56'



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 10/30/97