

**SURVEY & REMONUMENTATION**

MAR 03 1998

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**  
**KENT COUNTY**

Located In:	Corner Code #
T 5N R 9W	B-10
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

1. Public Land Survey  
2. Property Controlling in Section  
3. Miscellaneous Property in Sec.  
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on June 13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

REC. OF DEEDS

*[Signature]*

97 OCT 14 AM 10:01

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

10020

Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:

- B-10 1830---GLO---Not Set
- 1972---Williams & Works---Set "T" Iron at intersection of 1/4 lines.  
14" Oak S50°W 30.20' 8" Oak N28°W 51.10' 8" Oak N63°W 25.10'  
Fence corner 2.2' S. & 21.5' W.
- 1972---LCRC #232---Spicer---Found "T" Iron - same wits. as W & W
- 1973---Survey---Chambers---"T" Iron per LCRC #232
- 1979-87---Surveys---Exxel Eng.---"T" Iron per LCRC #232

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

B-10 Found "T" Iron per witnesses to C/L of trees of LCRC #232 that is 0.3' N. & 0.1' W. from intersection of 1/4 lines.

Also found Capped Rerod (Exxel) that is 0.5' S. & 0.2' W. from int. of 1/4 lines.

Word from Exxel is that their surveys don't indicate setting anything else at this corner.

The "T" Iron per LCRC #232 is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-10 Set Standard Kent Co. Monument (Harrison) in place of the "T" Iron
- Nail & KC Remon. tag SE side 24" Oak S50°W 30.01'
- Nail & KC Remon. tag SW side 15" Oak N65°W 25.06'
- Nail & KC Remon. tag W. side 15" Oak N25°W 51.09'
- Nail & KC Remon. tag W. side 8" Oak N10°E 33.36'
- Nail & KC Remon. tag N. side 10" Cherry S85°E 48.65'
- Capped Rerod (Exxel) South 0.73'
- Fence E-W is South 2'±.
- Fence N-S is West 21'±.



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 8/28/97

P.A. 345 1990 KENT COUNTY

PEER APPROVED 7/29/97  
CHAIRMAN *Harry Hubert*