

**SURVEY & REMONUMENTATION**

MAR 03 1998

KENT COUNTY REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**  
**KENT COUNTY**

Located In: Corner Code #

1. Public Land Survey	T 5N R 9W	B-11
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 APR 29 AM 8:17  
REG. OF DEEDS  
*Lucy Bond*

9709

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Feb. 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-11	1830	GLO	Mullett	Set Post
		Kent Co. Wit.		Iron
	1972	LCRC #233	Spicer	1" Iron
	1978	LCRC #1142	Bonnema	3/4" Iron
	1981	LCRC #2494	Bonnema	Set Kent County Monument
	1990	LCRC #5336	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Douglas W. Bonnema on 11/25/81 and was recorded per LCRC #2494

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Douglas W. Bonnema in place of the 3/4" Iron he found. Said Iron checks with Kent Co. Wit. and LCRC's #233 & #1142.

LCRC #2494

Nail & tag 6" Ash N05°E	16.43'
Nail & tag 6" Ash N85°W	9.71'
Nail & tag 20" Oak S05°W	24.20'
Nail & tag 26" Ash S90°E	57.83'
S. edge Coldwater Riv. N 95'±	

LCRC #5336

Nail & tag 10" Ash S48°W	14.63'
Nail & tag 8" Ash N10°E	16.44'
Nail & tag 8" Ash N82°W	9.72'
Nail & tag 24" Oak S07°W	24.20'
Nail & tag 28" Ash S86°E	57.88'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11 Standard Kent County Monument

Nail & KC Remon. tag NW side 12" Maple	S48°W	14.63'
Nail & KC Remon. tag W. side 10" Ash	N10°E	16.44'
Nail & KC Remon. tag N. side 10" Ash	N82°W	9.72'
Nail & KC Remon. tag W. side 24" Oak	S07°W	24.20'
Nail & KC Remon. tag S. side 30" Ash	S86°E	57.85'

On fence line North-South  
Fence to East is 2' South  
South edge Coldwater River is North 95'±



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 3/27/97  
CHAIRMAN *Harry Hubert*