

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

| | | | | | |
|------------------------------------|---|----|---|----|-----|
| 1. Public Land Survey | T | 5N | R | 9W | C-6 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

REG. OF DEEDS

10003

97 JUN -3 AM 8:12

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Apr. 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

| | | | | |
|-----|------|------------|-----------|--------------------------|
| C-6 | 1830 | GLO | Mullett | Set Post |
| | 1975 | LCRC #844 | Nederveld | Set 3/4" Solid Iron |
| | 1986 | LCRC #4417 | Jonker | Set Kent County Monument |
| | 1990 | LCRC #5342 | Starr | Kent County Monument |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 4/8/86 and was recorded per LCRC #4417

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-6 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 3/4" Solid Bar he found. Said Solid Bar checks with LCRC #844 and Consumers Power Co. Information.

| | |
|-------------------------------------|---|
| <u>LCRC #4417</u> | <u>LCRC #5342</u> |
| "X" cut on conc. culv. N70°E 26.75' | Nail & tag 8" Box Elder S42°E 40.17' |
| "X" cut on conc. culv. N60°W 26.69' | Nail & tag Tri. 4"-4"-8" B. Elder S18°W 104.05' |
| Remon. tag 10" Elm S35°W 66.44' | Nail & tag 10" Oak S66°W 55.56' |
| Remon. tag 8" Twin Elm S75°E 43.47' | "X" cut on conc. culv. N67°E 26.69' |
| | "X" cut on conc. culv. N57°W 26.72' |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | | |
|---|-------|---------|
| C-6 Standard Kent County Monument | | |
| Nail & KC Remon. tag SW side Tri. 10" Box Elder | S42°E | 40.24' |
| Nail & KC Remon. tag W. side 12" Box Elder | S18°W | 103.58' |
| Nail & KC Remon. tag NW side 14" Oak | S66°W | 55.31' |
| "X" cut on East end 48" conc. culv. | N67°E | 26.69' |
| "X" cut on West end 48" conc. culv. | N57°W | 26.72' |
| Corner is 0.8'± East of C/L blacktop road. | | |



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 5/22/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 5/22/97
CHAIRMAN Harvey Huber