

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>5N</u> R <u>9W</u>	C-11
	T <u> </u> R <u> </u>	_____
	T <u> </u> R <u> </u>	_____
	T <u> </u> R <u> </u>	_____
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	_____
	S <u> </u> T <u> </u> R <u> </u>	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 APR 29 AM 8:17
REG. OF DEEDS
Luci Bond

9718

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

C-11	1830	GLO	Mullett	Set Post
		Kent Co. Wit.		Mon. Box
	1972	LCRC #233	Spicer	3/4" Iron in Mon. Box
	1972	LCRC #259	Bonnema	3/4" Iron in Mon. Box
	1981	LCRC #2486	Bonnema	Set Kent County Monument in Mon. Box
	1990	LCRC #5347	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Douglas W. Bonnema on 11/25/81 and was recorded per LCRC #2486

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


C-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Douglas W. Bonnema in place of the 3/4" Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wit. and LCRC's #233 & #259.

<u>LCRC #2486</u>	<u>LCRC #5347</u>
Nail & tag 12" Maple N10°W 172.63'	Nail & tag Serv. Pole N15°W 144.32'
Nail & tag 10" Pine N25°E 192.61'	Nail & tag fc. post N30°E 70.16'
Nail & tag fc. post East 33.34'	Nail & tag 5" Catalpa N88°W 42.10'
Nail & tag P. Pole S15°E 185.56'	Nail & tag fc. post S88°E 33.81'
Nail & tag 12" Elm S35°W 101.23'	Nail & tag P. Pole S15°E 185.64'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11 Standard Kent County Monument in Mon. Box	
Nail & KC Remon. tag E. side Service Pole	N15°W 144.37'
Nail & KC Remon. tag NW side fence post (leaning)	N30°E 70.16'
Nail & KC Remon. tag N. side 12" Catalpa	N88°W 42.05'
Nail & KC Remon. tag W. side Power Pole	S15°E 185.64'
Nail & KC Remon. tag S. side fence post (newer)	S85°E 34.76'
On fence line to East and on brush row to West	



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN *Harry Huber*