

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

Located In: Corner Code #

1. Public Land Survey	T <u>5N</u> R <u>9W</u>	C-12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 97 APR 29 AM 8:17
 REG. OF DEEDS
Luis J. Bond

9719

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		9		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-12	1830	GLO	Mullett	Set Post
	1970	Kent Co. Wit.		Mon. Box
	1972	LCRC #259	Bonnema	3/4" Iron in Mon. Box
	1975	LCRC #846	Nederveld	1" Iron in Mon. Box
	1981	LCRC #2489	Bonnema	Set Kent County Monument in Mon. box
	1990	LCRC #5348	Starr	Kent County Monument in Mon. Box

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Douglas W. Bonnema on 11/25/81 and was recorded per LCRC #2489

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-12 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Douglas W. Bonnema in place of the 1" Iron he found inside a Mon. Box. Said Iron checks with Kent Co. Wit. and LCRC's #259 & #846.

<u>LCRC #2489</u>		<u>LCRC #5348</u>
Nail & tag 14" Elm	N20°W 86.38'	Nail & tag 18" Elm N18°W 86.14'
Nail & tag 30" Ash	East 90.81'	Nail & tag P. Pole S88°E 62.61'
Nail & tag 10" dbl. Ash	S65°E 64.28'	Nail & tag Fc. Post S31°E 89.99'
Nail & tag 6" Tw. Ash	N65°E 44.18'	Nail & tag Tw. 6" Elm N63°E 44.18'
		Nail & tag Tri. 12" Ash S65°E 64.29'


The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-12 Standard Kent County Monument in Mon. Box

Nail & KC Remon. tag E. side 26" Elm	N18°W 85.91'
Nail & KC Remon. tag N. side stump pole	S88°E 62.61'
Nail & KC Remon. tag W. side fence post	S31°E 89.99'
Nail & KC Remon. tag SW side Quad 12"-20" Ash	S65°E 64.29'
Nail & KC Remon. tag NW side P. Pole	S55°W 55.07'

On C/L N-S blacktop road and on fence lines E-W



Signed by *Kirk Breitels*
 Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 3/27/97
 CHAIRMAN *Harry Huber*