

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

Located In:	Corner Code #
T 5N R 9W	D-6
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

97 NOV 13 PM 1:06

REG. OF DEEDS
[Signature]
10262

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Sept. 9 97, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- D-6 1830---GLO---Not Set
- 1906---Williams & Works---Survey N 1/2 of Section, no notation of what was found or used.
- Kent Co. Wits.---No information
- 1977---Survey---Consumers Power Co.---Intersection of 1/4 lines
- 1981---Survey---Exxel Eng.---Intersection of 1/4 lines

P.A. 345 1990 KENT COUNTY
PEER APPROVED 9/25/97
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-6 Established Intersection of 1/4 lines and found nothing.
 - Fence corner for fences E-W & N is 8' N. and 4' W.
- Measurements to 1/4 corners agrees ± with CP Co. & Exxel.

The Intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-6 Set Standard Kent Co. Monument (Harrison) at the Intersection of 1/4 lines.
- Nail & KC Remon. tag N. side 27" Maple N65°W 42.57'
- Nail & KC Remon. tag W. side 36" Maple N30°E 11.76'
- Nail & KC Remon. tag S. side 8" Pine S55°E 40.93'
- Nail & KC Remon. tag W. side 12" Pine S30°W 32.00'



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 10/30/97