

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

MAR 03 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

SECTION

Located In:

Corner Code #

(County)

1. Public Land Survey

T 5N R 9W

D-7

T R

T R

T R

T R

2. Property Controlling in Section

S

T R

S

T R

3. Miscellaneous

S

T R

Property in Sec.

S

T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 24, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

REG. OF DEEDS
97 APR 29 AM 8:17
STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
9724
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

D-7	1830	GLO	Mullett	Set Post
	1968	Kent Co. Wit.		Iron
	1981	LCRC #1811	Bonnema	Capped Rerod
	1982	LCRC #2858	Jonker	Set Kent County Monument
	1990	LCRC #5352	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 5/14/82 and was recorded per LCRC #2858

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


D-7 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the Capped Rerod he found. Said Rerod checks with Kent Co. Wit. and LCRC #1811.

<u>LCRC #2858</u>		<u>LCRC #5352</u>	Nail & tag 14" Locust	S76°W	80.86'
Remon. tag P. Pole	S65°E	107.94'	Nail & tag Tw. 8" Locust	S25°E	31.50'
Remon. tag 6" Locust	N40°E	39.52'	Nail & tag 8" Locust	N04°W	37.77'
Remon. tag 8" Oak	S10°E	67.26'	Nail & tag P. Pole	S63°E	107.96'
Remon. tag 10" Locust	S75°W	80.97'	Nail & tag 8" Locust	N41°E	39.55'
			Nail & tag 8" Poplar	S52°W	39.32'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-7	Standard Kent County Monument				
	Nail & KC Remon. tag N. side 18" Locust	S76°W	80.80'		
	Nail & KC Remon. tag W. side Twin 10" Locust	S25°E	31.41'		
	Nail & KC Remon. tag E. side 10" Locust	N04°W	37.74'		
	Nail & KC Remon. tag NE side Power Pole	S63°E	107.96'		
	Nail & KC Remon. tag SE side 12" Locust	N41°E	39.51'		
	Nail & KC Remon. tag NW side 16" Poplar	S52°W	39.28'		
	C/L E-W bit. road is 3'± North				



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN Harry Huber