

**SURVEY & REMONUMENTATION**

**KENT COUNTY REMONUMENTATION**

**MAR 03 1998**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
57 APR 29 AM 8:17  
REG. OF DEEDS  
*Lucy Bond*

For corners in SECTION  
KENT COUNTY

Located In:	Corner Code #
1. Public Land Survey T 5N R 9W	D-9
T R	
T R	
T R	
2. Property Controlling in Section S T R	
S T R	
3. Miscellaneous Property in Sec. S T R	
S T R	

**9725**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-9	1830	GLO	Mullett	Set Post
		Kent Co. Wit.		Boat Spike
	1973	LCRC #483	Spicer	Boat Spike
	1981	LCRC #2493	Bonnema	Set Kent County Monument
	1990	LCRC #5353	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Douglas W. Bonnema on 11/25/81 and was recorded per LCRC #2493

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-9 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Douglas W. Bonnema in place of the Boat Spike he found. Said Boat Spike checks with Kent Co. Wit. and LCRC #483.

LCRC #2493

LCRC #5353

Nail & tag 40" Oak	S75°W	77.36'	Nail & tag P. Pole	N02°E	47.97'
Nail & tag 6" Cherry	N65°W	56.64'	Nail & tag 40" Oak	S75°W	77.43'
Nail & tag 18" Oak	S30°W	35.04'	Nail & tag 18" Oak	S32°W	35.03'
Nail & tag 18" Willow	S20°E	34.02'	Nail & tag 20" Willow	S17°E	34.02'
Nail & tag 24" Willow	S70°E	77.41'	Nail & tag 30" Willow	S70°E	77.61'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9 Standard Kent County Monument

Nail & KC Remon. tag W. side P. Pole	N02°E	48.00'
Nail & KC Remon. tag SE side 42" Oak	S75°W	77.43'
Nail & KC Remon. tag E. side 22" Oak	S32°W	35.06'
Nail & KC Remon. tag W. side 26" Willow	S17°E	34.05'
Nail & KC Remon. tag N. side 36" Willow	S70°E	77.70'

On fence line N-S and on C/L E-W bit. road



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/27/97

CHAIRMAN *Harry Kupers*