

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

SECTION

	Located In:	Corner Code #
1. Public Land Survey	T 5N R 9W	D-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 97 APR 29 AM 8:17
 REG. OF DEEDS
Lucy Bond

9726

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-11	1830	GLO	Mullett	Set Post
		Kent Co. Wit.		3/4" Iron
	1972	LCRC #259	Bonnema	3/4" Iron
	1973	LCRC #483	Spicer	1" Iron
	1981	LCRC #2492	Bonnema	Set Kent County Monument
	1990	LCRC #5354	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Douglas W. Bonnema on 11/25/81 and was recorded per LCRC #2492

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Douglas W. Bonnema in place of the 3/4" Iron he found. Said Iron checks with Kent Co. Wit. and LCRC's #259 & #483.

<u>LCRC #2492</u>		<u>LCRC #5354</u>	
Nail & tag 12" Ash	South 14.23'	Nail & tag 8" Ash	N23°E 35.55'
Nail & tag 26" Ash	S85°W 10.27'	Nail & tag 14" Ash	South 14.24'
Nail & tag 12" Ash	S60°E 5.40'	Nail & tag 30" Ash	S89°W 10.27'
Nail & tag 12" Elm	N50°W 10.93'	Nail & tag dbl. 8"-10" Ash	S68°E 5.36'
Nail & tag 18" Ash	S60°W 61.34'	Nail & tag dead 12" Elm	N44°W 10.95'
		Nail & tag 18" Ash	S60°W 61.37'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>D-11 Standard Kent County Monument</u>	
Nail & KC Remon. tag E. side 10" Ash	N23°E 35.55'
Nail & KC Remon. tag W. side 16" Ash	South 14.24'
Nail & KC Remon. tag S. side 32" Ash	S89°W 10.27'
Nail & KC Remon. tag SW side dbl. 8"-10" Ash	S68°E 5.36'
Nail & KC Remon. tag SW side stump	N44°W 10.95'
Nail & KC Remon. tag SE side 20" Ash	S60°W 61.37'
East edge Coldwater River is West 52'±	



Signed by *Kirk Breitels*
 Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 3/27/97
 CHAIRMAN *Harry Fisher*