

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

Located In: Corner Code #

1. Public Land Survey	T 5N R 9W	E-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 APR 29 AM 8:18
REG. OF DEEDS
Lucy Bond

9731

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-4	1830	GLO	Mullett	Set Post
	1975	LCRC #1005	Nederveld	1" Round Iron-Set "T" Iron over
	1982	LCRC #2667	Bonnema	Set Kent County Monument
	1990	LCRC #5358	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Douglas W. Bonnema on 2/19/82 and was recorded per LCRC #2667

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-4 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Douglas W. Bonnema in place of the "T" Iron he found. Said "T" Iron checks with LCRC #1005.

<u>LCRC #2667</u>		<u>LCRC #5358</u>	
Nail & tag 26" Cherry	S90°W 52.65'	Nail & tag 20" Cherry	S90°W 52.69'
Nail & tag 28" Cherry	S20°W 65.82'	Nail & tag 34" Maple	N14°W 95.24'
Nail & tag 34" Maple	N15°W 95.24'	Nail & tag 8" Apple	S75°E 36.60'
Nail & tag 4" Apple	S85°E 36.59'	Nail & tag 8" Apple	S26°E 74.19'
Nail & tag 6" Apple	S40°E 74.24'	Nail & tag 26" Oak	S30°W 65.83'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4 Standard Kent County Monument	
Nail & KC Remon. tag S. side 24" Cherry	S90°W 52.65'
Nail & KC Remon. tag E. side 38" Maple	N14°W 95.24'
Nail & KC Remon. tag E. side 30" Oak	S30°W 65.83'
SW corner conc. support of tank	N70°E 63.16'
C/L N-S blacktop road is East 3'±	
On tree line West	



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN *Dan Huber*