

**SURVEY & REMONUMENTATION**

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY

Located In: Corner Code #

1. Public Land Survey	T	5N	R	9W	E-8
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 APR 29 AM 8:18  
REG. OF DEEDS  
*Luis J. Bond*  
9733  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-8	1830	GLO	Mullett	Set Post
	1963	Kent Co. Wit.		Concrete Monument
	1984	LCRC #4060	Jonker	Set Kent County Monument in Mon. Box
	1990	LCRC #5361	Starr	Kent County Monument in Mon. Box

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 12/14/84 and was recorded per LCRC #4060

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


E-8 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the Concrete Monument he found. Said Concrete Monument checks with Kent Co. Wit.

<u>LCRC #4060</u>	NW cor. base fc. post	N90°E	32.78'	<u>LCRC #5361</u>	NW cor. base fence post	S87°E	32.77'
	Remon. tag 12" Hickory	S15°E	123.84'		Nail & tag 14" Willow	N16°E	115.14'
	Remon. tag 10" Cherry	N45°W	35.85'		Nail & tag 14" Cherry	N42°W	35.78'
	Remon. tag 14" Oak	N15°E	154.25'		Nail & tag 14" Hickory	S12°E	123.80'
					On C/L N-S bit. road		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-8	Standard Kent County Monument in Mon. Box
NW cor. of base of steel corner fence post	S87°E 32.77'
Nail & KC Remon. tag W. side 20" Willow	N16°E 114.95'
Nail & KC Remon. tag NE side 18" Cherry	N42°W 35.78'
Nail & KC Remon. tag W. side 18" Hickory	S12°E 123.60'
On C/L N-S bit. road	



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 3/27/97  
CHAIRMAN *Harry Hubert*