

**SURVEY & REMONUMENTATION**

MAR 03 1998

**KENT COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located In: Corner Code #

1. Public Land Survey	T 5N R 9W	E-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 97 JUN -3 AM 8:12  
 REG. OF DEEDS  
*Lucy Bond*

**10006**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Apr. 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

E-9	1830	GLO	Mullett	Set Post
	1963	Kent Co. Wit.		Monument
	1982	LCRC #2935	Bonnema	Pinched Iron in Mon. Box
	1982	LCRC #3134	Bonnema	Set Kent County Monument
	1990	LCRC #5362	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Douglas W. Bonnema on 11/9/82 and was recorded per LCRC #3134.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-9 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Douglas W. Bonnema in place of the Pinched Iron and Conc. Mon. he found inside a Mon. Box. Said Iron and Conc. Mon. checks with Kent Co. Wit. and LCRC #2935.

<u>LCRC #3134</u>		<u>LCRC #5362</u>	
Nail & tag P. Pole	N48°E 87.40'	Nail & tag P. Pole	N52°E 87.42' Nail & tag
Nail & tag 24" Maple	N11°E 120.24'	"X" on conc. hdwll.	S23°W 62.13' 42" Oak
PK Nail in curb joint	N36°W 31.21'	"X" on conc. hdwll.	S15°E 61.30' N08°E 159.79'
"X" on conc. headwall	S20°W 62.16'	Nail & tag g. post	N25°W 38.95'
"X" on conc. headwall	S20°E 61.14'	Nail & tag top fc. post	S67°W 66.56'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9 Standard Kent County Monument			
Nail & KC Remon. tag E. side 48" Oak	N08°E	159.79'	
Nail & KC Remon. tag NW side P. Pole	N52°E	87.42'	
"X" on N. end conc. headwall (broken)	S23°W	62.32'	
"X" on N. end conc. headwall	S15°E	61.13'	
Nail & KC Remon. tag in top cor. fc. post	S67°W	65.67'	
On C/L N-S & E-W asphalt roads			



Signed by *Kirk Breitels*  
 Surveyor's Michigan License No. 30077

Date 5/22/97

P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 5/22/97  
 CHAIRMAN *Harold Kuehn*