

APR 27 1995

COMMISSION

Kent County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 94 DEC 30 PM 12:06

W. J. Jones
 REG. OF DEEDS

For corners in

<u>Kent County</u> (County)	Located In: Bowne Twp.	Corner Code # F-2
1. Public Land Survey	T 5N R 9W	
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

7966
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert Jonker, in a field survey on December 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Not set in GLO survey
 1941 - K.C. wit. map - 1" iron over plow point
 W&W - 1955 - Found & accepted boat spike per witnesses
 W&W - 1961 - Ran 1/4 lines - Found boat spike to be 10.7' E & 7.5' N of int. of 1/4 lines, accepted boat spike
 W&W - 1973 - Found boat spike, used, took wit. & recorded LCRC #941 in 1976
 Prein & Newhof - 1988 - Boat spike in mon. box - recorded in LCRC #4553

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found boat spike in mon. box (raised over plow point) per wit. for LCRC's in "A" above.

Verified position with respect to 1/4 lines as per W&W in 1961.

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 12/15/94
 CHAIRMAN *Harry Hubers*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed boat spike and set 4" standard K&C Harrison monument.

- K.C. N&T W. side P. pole S° 0° 66.76'
- K.C. N&T NW side 46" Oak N 45° E 67.28'
- K.C. N&T E. side P. pole N 30° E 105.89'
- K.C. N&T E. side 20" Hickory N 5° E 88.20'
- R.R. spike @ C/L "X" of roads S80° E 28.08'
- C/L E-W road is 5' South
- C/L road to North is 27 1/2' ± East

Signed by Robert J. Jonker Date December 28, 1994
 JONKER LAND SURVEYS, P.C. 21572
 Surveyor's Michigan License No. _____