

SURVEY & REMONUMENTATION

APR 27 1995

Kent County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 94 DEC 30 PM 12:06

COMMISSION

For corners in

<u>Kent County</u> (County)	Located In: Bowne Twp.	Corner Code # F-8
1. Public Land Survey	T <u>5N</u> R <u>9W</u>	<u>F-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Luigi J. Bond
 REG. OF DEEDS

7972

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Robert Jonker, in a field survey on December 22, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Not set in GLO survey.
 No info. from W & W and other firms.

P.A. 345 1990 KENT COUNTY
 PEER APPROVED 12/22/94
 CHAIRMAN *Harry Husher*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set @ intersection of $\frac{1}{4}$ lines.

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4" standard K.C. Harrison monument.
 K.C. N&T E. side 30" Tri.W.Cherry N 25° E 31.60'
 K.C. N&T S. side 24" Ash N 90° E 25.56'
 K.C. N&T E. side 24" Oak S 15° E 30.97'
 K.C. N&T E. side 20" Hickory S 20° W 74.34'
 K.C. N&T S. side 24" Oak N 85° W 33.15'
 At intersection of N, S, E, W, fences



Signed by Robert J. Jonker
 JONKER LAND SURVEYS, P.C.
 Surveyor's Michigan License No. 21572

Date December 28, 1994