

**SURVEY & REMONUMENTATION**

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

REG. OF DEEDS

*David J. ...*

97 APR 29 AM 8:18

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

For corners in  
KENT COUNTY

Located In: Corner Code #

1. Public Land Survey	T 5N R 9W	F-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

9740

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 28, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-9	1830	GLO	Mullett	Set Post
	1944	Kent Co. Wit.		Iron
	1981	LCRC #1626	Byl	Pinched Pipe in Mon. Box
	1986	LCRC #4415	Jonker	Set Kent County Monument in Mon. Box
	1990	LCRC #5370	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 4/8/86 and was recorded per LCRC #4415.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-9 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the Pinched Pipe he found inside a Mon. Box. Said Pinched Pipe checks with Kent Co. Wit. and LCRC #1626.

<u>LCRC #4415</u>	Remon. tag 6" Tw. Elm	N60°W	74.15'	<u>LCRC #5370</u>	Remon. tag 6" Tw. Elm	N60°W	74.15'
	Remon. tag 24" Walnut	North	33.47'		Remon. tag 24" Walnut	North	33.47'
	Spike 6" Maple	N70°E	71.70'		Nail & tag P. Pole	S50°W	31.11'
	NW cor. hse. fnd.	South	94.95'		Nail & tag 6" Maple	N70°E	71.86'
					NW cor. hse. fnd.	South	95.10'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9 Standard Kent County Monument	Nail & KC Remon. tag NE side 10" Tw. Elm	N60°W	74.15'
	Nail & KC Remon. tag W. side 27" Walnut	North	33.46'
	Nail & KC Remon. tag NW side P. Pole	S50°W	31.11'
	Nail & KC Remon. tag NW side 12" Maple	N70°E	71.86'
	NW corner house foundation	South	95.07'
	On fence & tree line to the North		
	C/L E-W pavement, North 1'		



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 3/27/97  
CHAIRMAN Harry Huber