

**SURVEY & REMONUMENTATION**

MAR 03 1998

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**  
**KENT COUNTY**

Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>9W</u> F-10
	T <u>    </u> R <u>    </u>
	T <u>    </u> R <u>    </u>
	T <u>    </u> R <u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

97 OCT 14 AM 10:30

REG. OF DEEDS  
*Lucy Bond*

10050

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on June 13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
F-10 1830---GLO---Not Set  
Williams & Works---No information  
Kent Co. Wits.---No information  
1982---Survey---Exxel Eng.---Capped Rerod  
12" Hickory S 15.88' 8" W. Cherry WSW 12.40'  
8" Oak SE 52.98' 50" Hickory NNW 94.19'  
Old fence corner 4' S. & 5' W.

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 7/24/97  
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
F-10 Found Capped Rerod per the following witnesses:  
Spike in 18" Hickory South 15.86' Spike in 12" Oak SE 52.96'  
Spike in 12" W. Cherry WSW 12.43' Spike in 50" Hickory NNW 94.19'  
Old fence corner (lying down) 4' S. & 5' W.

Capped Rerod is 0.2' N. & less than 0.1' E. of intersection of 1/4 lines.

The Capped Rerod is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
F-10 Set Standard Kent Co. Monument (Harrison) in place of the Capped Rerod  
Spike in W. side 18" Hickory S00°E 15.86'  
Nail & KC Remon. tag N. side 12" Cherry S85°W 12.43'  
Nail & KC Remon. tag S. side 12" Oak S50°E 52.96'  
Nail & KC Remon. tag E. side 30" Hickory N20°W 94.14'  
Old fence corner (lying down) is 4' S. & 5' W. ±



Signed by [Signature]  
Surveyor's Michigan License No. 30077

Date 9/23/97