

SURVEY & REMONUMENTATION

KENT COUNTY REMONUMENTATION

MAR 03 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 APR 29 AM 8:18
REG. OF DEEDS
Lucy Stand

For corners in **SECTION**
KENT COUNTY
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|---|-------|
| 1. Public Land Survey | T <u>5N</u> R <u>9W</u> | F-13 |
| | T <u> </u> R <u> </u> | _____ |
| | T <u> </u> R <u> </u> | _____ |
| | T <u> </u> R <u> </u> | _____ |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | _____ |
| | S <u> </u> T <u> </u> R <u> </u> | _____ |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | _____ |
| | S <u> </u> T <u> </u> R <u> </u> | _____ |

9741

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Mar. 13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-13	1830	GLO	Mullett	Set Post
	1963	Williams & Works		Set "T" Iron
	1973	LCRC #617	Spicer	3/4" Iron
	1986	LCRC #4419	Jonker	Set Kent County Monument
	1990	LCRC #5372	Starr	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 4/8/86 and was recorded per LCRC #4419

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 Found BROKEN standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the "T" Iron he found. Said "T" checks with Williams & Works information. LCRC #617 does not fit. RESET Kent Co. Mon. per LCRC #5372.
LCRC #4419
LCRC #5372 MVK Capped Iron-East 9.44'

PK Nail P. Pole	N05°E	32.85'	Nail & tag P. Pole	N04°E	32.84'
C/L USGS Benchmark	N50°W	29.33'	C/L USGS Benchmark	N55°W	29.42'
Remon. tag 8" Elm	S05°E	35.82'	Nail & tag 9" Elm	S03°E	35.80'
Sq. spike 8" Elm	S40°E	35.15'	Nail & tag 10" Maple	S45°W	29.16'
MVK capped Iron	East	9.49'	Nail & tag 8" Ash	S48°E	54.88'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 Standard Kent County Monument

Nail & KC Remon. tag W. side P. Pole	N04°E	32.84'
C/L USGS Benchmark	N55°W	29.42'
Nail & KC Remon. tag W. side 11" Elm	S03°E	35.83'
Nail & KC Remon. tag SE side 12" Oak	S45°W	29.21'
Nail & KC Remon. tag NE side 10" Ash	S48°E	54.91'
MVK Capped Rod	East	9.44'

On C/L E-W gravel road ±.



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN *Harry Huber*