

1
2
SURVEY & REMONUMENTATION
MAR 03 1998

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T 5N R 9W	H-1
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- Public Land Survey
- Property Controlling In Section
- Miscellaneous Property in Sec.

STATE OF MICHIGAN
COUNTY OF KENT
RECORDED FOR RECORD
97 OCT 14 AM 10:30
REG. OF DEEDS
Lucy Bond

10051
Register of Deeds Stamp & File Number

- Lot No. _____, Recorded Plat _____
- Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kirk Breitels, in a field survey on June 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-1 1830---GLO---Mullett---Not Set
 1914---Williams & Works---Point on fence to South - 60.7' East of fence to North
 1918---Williams & Works---Iron ?
 1952-54---Williams & Works---No corner found - Meas. 2639.60' NW corner to N 1/4 (1914-1918 location) - Used Iron 295' West of N 1/4 as located in 1914
 ---By1 Notes---Iron on fence line to South, 60' ± East of S 1/4 corner of Sec. 34, Lowell Twp.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-1 Found nothing at corner, large culvert under road at approx. location of H-1
 C 1/4, Sec. 3, 5-9, (Kent Co. Mon., LCRC #4508) was set at the "X" 1/4 lines using a N 1/4 corner, 60.7' East (comp. GLO jog 57.42') of the S 1/4 corner of Sec. 34, 6-9 per Section breakdown by M. Rosema.
 Established N 1/4 Sec. 3, 60.7' East of S 1/4 Sec. 34-6-9 and Meas. W. to NW cor.: 2640.27' - 2640.28' Rosema 1986 - 2639.60' WW 1952

The N 1/4 corner of Sec. 3, 5-9, being 60.70' feet East of the S 1/4 corner, Sec. 34, 6-9, is accepted by me and is generally accepted by professional surveyors as the best available evidence of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1 Set Standard Kent Co. Monument (Harrison) on Twp. Line per above.
 NE corner concrete foundation S35°W 94.68'
 Set Nail & KC Remon. tag NE side fence post (E'ly of 2) N45°W 61.05'
 Set Nail & KC Remon. tag NE side Power Pole N50°E 74.50'
 Set Nail & KC Remon. tag SW side Tw. 12" Maple S40°E 89.17'
 Kent Co. Mon. (H-13, T6N, R9W) West 60.70'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 6/26/97
 CHAIRMAN Harry Huber

Signed by Kirk Breitels
 Surveyor's Michigan License No. 30077

Date 9/15/97

