

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

T 5N R 9W H-2

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 APR 29 AM 8:18
REG. OF DEEDS
Lucy Bond

9748

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kirk Breitels, in a field survey on Jan. 29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-2	1830	GLO	Mullett	Not Set
	1913-52	Williams & Works		Section Information
	1987	LCRC #4508	Rosema	Set Kent County Monument
	1994	LCRC #7003	By I	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Maurice J. Rosema on 4/9/87 and was recorded per LCRC #4508.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-2 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Maurice J. Rosema at the intersection of 1/4 lines. Location checks with Williams & Works section information ±.

<u>LCRC #4508</u>				<u>LCRC #7003</u>			
Nail & tag Tw. 15" Ash	S38°E	36.78'		Nail & tag Tw. 18" Ash	S38°E	36.78'	
Nail & tag 8" Maple	N72°E	59.29'		Nail & tag 10" Ash	N72°E	59.37'	
Nail & tag 15" Maple	N14°E	32.62'		Nail & tag 18" Maple	N14°E	32.62'	
Nail & tag 24" Maple	S51°W	56.09'		Nail & tag 30" Maple	S51°W	56.05'	
				Rerod	S00°E	32.98'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-2 Standard Kent County Monument

Nail & KC Remon. tag E. side Tw. 18" Ash	S38°E	36.78'
Nail & KC Remon. tag SE side 14" Hickory	N72°E	59.37'
Nail & KC Remon. tag E. side 18" Maple	N14°E	32.62'
Nail & KC Remon. tag NW side 30" Maple	S51°W	56.05'
Rerod	S00°E	32.98'

N-S tree row is East 5'±
C/L E-W asphalt road is South 3'±



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN *Harry Stuber*