$7.00
$2.00

SURVEY & REMONUMENTATION

JAN 2 3 1996

COMMISSION

Kent County Remonumentation

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 DEC 26 PM 12: 43
REG. OF DEEDS

8872

Register of Deeds Stamp & File Number

For corners in Kent (County)

		Located In: Bowne Twp.	Corner Code ##
1. Public Land Survey		T 5N R 9W	H-6
		T ___ R ___	
		T ___ R ___	
		T ___ R ___	
2. Property Controlling	S ___	T ___ R ___	
in Section	S ___	T ___ R ___	
3. Miscellaneous	S ___	T ___ R ___	
Property in Sec.	S ___	T ___ R ___	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____



I, Robert J. Jonker, in a field survey on February 23, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner was not set in G.L.O. survey
No info. received from local surveyors
No info. on old K.C.R.C. witness map

Con. Power maps show holding int. of
¼ lines 1976 E. McCombs

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Checked at occupation lines, found nothing, set corner at intersection of ¼ lines.

West ¼ - West 2629.04'
North ¼ - North 2645.93'
East ¼ - East 2637.47'
South ¼ - South 2638.77'

P.A. 345 1990 KENT COUNTY
PEER APPROVED 4/27/95
CHAIRMAN Harry Huber

Approved by Kent County Peer Group, Apr.27,1995.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard 4" Kent County monument.

Nail & Remon Tag - W. side 10" Walnut	S 25°	W	28.35'
Nail & Remon Tag - N. side 10" Walnut	S 85°	W	27.66'
NW corner "L" fence post	S 75°	W	10.03'
C/L steel fence post	S 60°	E	5.2'

The E-W fence line is 2.5' South
Tree row to South is 10' West

STATE OF MICHIGAN
ROBERT J. JONKER
PROFESSIONAL SURVEYOR
No. 21572
LICENSED PROFESSIONAL SURVEYOR

Signed by Robert J. Jonker Date March 30, 1995
JONKER LAND SURVEYS
Surveyor's Michigan License No. 21572

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983