

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

Located In: Corner Code #

- | | | | | | |
|------------------------------------|---|----|---|----|------|
| 1. Public Land Survey | T | 5N | R | 9W | H-10 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 APR 29 AM 8:19
REG. OF DEEDS
W. Glaza

9752

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 10, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

H-10	1830	GLO	Mullett	Not Set
	1990	LCRC #5744	W. Glaza	Set Capped Rerod at int. 1/4 lines
	1991	LCRC #6205	W. Glaza	Set Kent County Monument
	1994	LCRC #7007	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Wallace Glaza on 11/1/91 and was recorded per LCRC #6205

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-10 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Wallace Glaza in place of the Capped Rerod he found. Said Capped Rerod checks with LCRC #5744.

<u>LCRC #6205</u>		<u>LCRC #7007</u>	
Nail & tag 24" Tw. Maple	N05°E 33.97'	Nail & tag 24" Tw. Maple	N05°E 34.00'
Nail & tag fence post	N30°E 4.17'	Nail & tag fence post	N30°E 4.19'
Nail & tag 28" Maple	N90°E 8.86'	Nail & tag 28" Maple	N90°E 8.86'
Nail & tag 28" Maple	S35°W 11.50'	Nail & tag 28" Stump	S35°W 11.50'
Nail & tag 18" Maple	S30°E 23.97'	Nail & tag 18" Maple	S30°E 23.97'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-10 Standard Kent County Monument			
Nail & KC Remon. tag W. side 24" Tw. Maple	N05°E	33.98'	
Nail & KC Remon. tag SE side fence post	N30°E	4.19'	
Nail & KC Remon. tag S. side 30" Maple	N90°E	8.82'	
Nail & KC Remon. tag SE side 28" stump	S35°W	11.50'	
Nail & KC Remon. tag W. side 20" Maple	S30°E	23.97'	



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN Harry Hubers