

**SURVEY & REMONUMENTATION**

MAR 03 1998

**SECTION**

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
KENT COUNTY  
(County)

Located In:	Corner Code #
T 5N R 9W	H-13
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 97 APR 29 AM 8:19  
 REG. OF DEEDS  
*Lucy Bond*

**9754**

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Feb. 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

H-13	1830	GLO	Mullett	Set Post
	1974	LCRC #759	Bonnema	1/2" Iron
	1981	LCRC #1712	Merdzinski	Set Kent County Monument
	1994	LCRC #7009	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 2/18/81 and was recorded per LCRC #1712

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

H-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1/2" Iron he found. Said Iron checks LCRC #759.

LCRC #1712			LCRC #7009		
Nail & tag 24" Oak	N70°W	97.81'	Nail & tag 30" Oak	N70°W	97.31'
Nail & tag 17" Tw. Oak	N10°W	116.63'	Nail & tag 20" Tw. Oak	N10°W	116.75'
Nail & tag 12" Walnut	S80°E	133.13'	Nail & tag 15" Walnut	S80°E	132.92'
Nail & tag top MBT Box	N45°E	90.30'	Top C/L MBT Box	N45°E	90.30'
Nail & tag 3" Elm clump	N25°E	91.70'	Nail & tag 6" Elm clump	N25°E	91.70'
Nail & tag 6" Elm	S20°E	133.52'	Nail & tag 12" Elm	S20°E	133.83'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

H-13 Standard Kent County Monument	
Nail & KC Remon. tag S. side 32" Maple	N70°W 97.31'
Nail & KC Remon. tag E. side 22" Tw. Maple	N10°W 116.75'
Nail & KC Remon. tag N. side 16" Walnut	S80°E 132.92'
C/L Top of MBT Box	N45°E 90.30'
Nail & KC Remon. tag W. side 10" Elm clump	N25°E 91.66'
Nail & KC Remon. tag SW side 14" Elm	S20°E 133.83'
Mon. is 1' E. of C/L bit. rd. N-S and 8' S. of C/L grav. rd. E-W	



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 3/27/97  
CHAIRMAN *Harry Hubert*