

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 97 APR 29 AM 8:19
 REG. OF DEEDS
Lucy Bond

For corners in
KENT COUNTY

Located in:

Corner Code #

1. Public Land Survey		T <u>5</u> N	R <u>9</u> W		I-4
		T	R		
		T	R		
		T	R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

9757

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-4	1830	GLO	Mullett	Set Post
	1937	Kent Co. Wit.		Iron & Stone
	1980	LCRC #1336	Byl	Mon. Box
	1981	LCRC #2247	Jonker	Set Kent County Monument in Mon. Box
	1994	LCRC #7012	Byl	Kent County Monument in Mon. Box

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 11/6/81 and was recorded per LCRC #2247

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
I-4 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1" Iron he found inside a Mon. Box. Said Iron checks with LCRC #1336.

<u>LCRC #2247</u>							
Remon. tag P. Pole	S42°W	54.3'	Nail & tag P. Pole	S42°W	54.30'		
Remon. tag fc. post	S87°E	31.73'	Nail & tag fc. post	S87°E	31.85'		
Remon. tag P. Pole	N08°W	197.17'	Nail & tag P. Pole	N08°W	197.17'		
C/L stop sign	S76°W	51.1'	Nail & tag 8" Elm clust.	S20°E	78.37'		
C/L st. sign	N43°W	41.3'					

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-4	Standard Kent County Monument					
	Nail & KC Remon. tag NW side P. Pole (leaning)	S42°W	54.17'			
	Nail & KC Remon. tag N. side fence post	S87°E	31.85'			
	Nail & KC Remon. tag E. side P. Pole	N08°W	197.17'			
	Nail & KC Remon. tag NE side 8" Elm cluster	S20°E	78.37'			
	On C/L N-S blacktop road and on l/m C/L grav. road West					



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 3/27/97
CHAIRMAN *Harry Hubert*