

**SURVEY & REMONUMENTATION**

**MAR 03 1998**

**KENT COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KENT COUNTY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>9W</u>	<u>I-6</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
 COUNTY OF KENT  
 RECEIVED FOR RECORD  
 97 APR 29 AM 8:19  
 REG. OF DEEDS  
*Lucy Bond*

**9759**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15	●	14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-6	1830	GLO	Mullett	Set Post
	1937	Kent Co. Wit.		3/4" Iron
	1986	LCRC #3441	McCombs	Pipe in Mon. Box
	1986	LCRC #3601	Kolehouse	Set Kent County Monument in Mon. Box
	1994	LCRC #7014	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 11/5/83 and was recorded per LCRC #3601

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the 3/4" Iron over Plow Point and Stones he found inside a Mon. Box. All check with LCRC #3441. All Kent Co. Wit. were gone.

<u>LCRC #3601</u>		<u>LCRC #7014</u>
Nail & tag P. Pole	West 48.77'	Nail & tag P. Pole S90°W 48.75'
Nail & tag 8" Cherry	S40°W 47.45'	Nail & tag 8" Cherry S40°W 47.67'
Nail & tag 12" Cherry	S15°W 107.65'	Nail & tag 12" Cherry S15°W 107.83'


The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6 Standard Kent County Monument

Nail & KC Remon. tag N. side P. Pole	S90°W	48.75'
Nail & KC Remon. tag NW side 12" Cherry	S40°W	47.67'
Nail & KC Remon. tag W. side 20" Cherry	S15°W	107.83'
Nail & KC Remon. tag S. side 20" Cherry	S75°W	29.88'

On fence line running West  
 In C/L Wingeier Ave. running N-S



Signed by *Kirk Breitels* Date 3/27/97

Surveyor's Michigan License No. 30077  
 P.A. 345 1990 KENT COUNTY  
 PEER APPROVED 3/27/97  
 CHAIRMAN *Harry Huber*