

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|---|---|----|-----|
| 1. Public Land Survey | T | N | R | 9W | I-9 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

REG. OF DEEDS

Luigi Bond

97 OCT 14 AM 10:02

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

10027

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on June 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

I-9 1830---GLO---Mullett---Set Post
---Williams & Works---No information
---Kent Co. Wits---Boat Spike
NW cor. HW ESE 59.02' NW cor. HW ENE 59.35'
CP Pole NE 48.94' Face steel fc. post NW 36.92'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-9 Found "T" Iron in Mon. Box at C/L 92nd St. & Wingeier Ave.

Fits one remaining witness ±:
Face Stump Pole NE 48.9'±
Hdwalls ENE & ESE gone ? - now C.M.P. culverts

The "T" Iron in Mon. Box is accepted by me and is generally accepted by professional surveyors as the best available evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9 Set Standard Kent Co. Monument (Harrison) in Mon. Box in place of the "T" Iron
"X" on top W. end conc. culv. S15°W 68.47'
"X" on top S. end conc. culv. S50°W 42.72'
"X" on top N. end conc. culv. N60°W 39.06'
Set Nail & KC Remon. tag SE side P. Pole N45°E 48.03'
PK Nail top S. end C.M.P. culv. S70°E 64.70'
"X" top E. end conc. culv. S20°E 68.26'



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 8/28/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/26/97
CHAIRMAN *Harry Hubert*