

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**
KENT COUNTY

Located In:	Corner Code #
1. Public Land Survey	T 5N R 9W I-10
	T R
	T R
	T R
2. Property Controlling in Section	S T R
	S T R
3. Miscellaneous Property in Sec.	S T R
	S T R

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
97 OCT 14 AM 10:02
REG. OF DEEDS
Lucy J. Bond

10028

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on June 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-10 1830---GLO---Mullett---Set Post
---Williams & Works---No information
1939---Kent Co. Wits---Monument
26" Maple E 21.25 26" Maple SE 46.2' 18" Hickory SW 73.5'
I-beam fc. post W 20.9' 10" Basswood NNE 61.65'
1990---LCRC #5744---W. Glaza---Concrete Monument 1.1' below surface
30" Maple E 22.0' Steel fc. post W 21.31' 30" Maple SSE 47.37'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10 Found Concrete Monument 1'± deep per following witnesses:

Nail/tag N. side 30" Maple E 22.03' C/L 24" Hickory SSW 74'±
NE cor. I-beam fc. post W 21.01'
C/L 36" Maple SSE 48'± Exxel Iron West 33'
Fence to West is 1'± South
On tree row East

The Concrete Monument is accepted by me and is generally accepted by professional surveyors as the best available evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10 Set Standard Kent Co. Monument (Harrison) on top of remains of Conc. Mon.
Set Nail & KC Remon. tag N. side 30" Maple East 22.03'
NE corner steel I-beam fence post West 21.01'
Set Nail & KC Remon. tag NE side 36" Maple S35°E 47.82'
Set Nail & KC Remon. tag SE side 10" Hickory S50°W 29.19'
Set Nail & KC Remon. tag NE side 6" Hickory N25°W 41.82'
Capped Rerod (Exxel) West 33.00'
C/L N-S asph. rd. is West 1.5'±



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 8/28/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/26/97
CHAIRMAN *Harry J. Hubell*