

**SURVEY & REMONUMENTATION**

MAR 03 1998

**KENT COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>5N</u> R <u>9W</u>	I-11
	T <u>   </u> R <u>   </u>	_____
	T <u>   </u> R <u>   </u>	_____
	T <u>   </u> R <u>   </u>	_____
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	_____
	S <u>   </u> T <u>   </u> R <u>   </u>	_____
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	_____
	S <u>   </u> T <u>   </u> R <u>   </u>	_____

REC. OF DEEDS

*Lucy Spauld*

97 APR 29 AM 8:19

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

9762

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Feb. 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-11	1830	GLO	Mullett	Set Post
	1946	Kent Co. Wit.		Monument
	1974	LCRC #746	Bonnema	3/4" Iron
	1981	LCRC #2248	Jonker	Set Kent County Monument
	1994	LCRC #7016	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 11/6/81 and was recorded per LCRC #2248

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 3/4" Iron over a Conc. Monument he found. Iron and Conc. Monument check with Kent Co. Wit. and LCRC #746.

<u>LCRC #2248</u>	Remon. tag cor. fc. post	S00°W 33.38'	Nail & tag cor. fc. post	S00°W 33.48'
	Remon. tag 36" Oak	N73°W 134.18'	Nail & tag 40" Oak	N73°W 134.08'
	Remon. tag 8"-10" B'wood	S74°W 61.40'	Nail & tag 12"-15" B'wood	S74°W 61.30'
	"X" on E. end culvert	N22°E 48.76'	"X" on E. end culvert	N22°E 48.76'
	"X" on W. end culvert	N21°W 49.94'	"X" on W. end culvert	N21°W 50.05'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11 Standard Kent County Monument	
Nail & KC Remon. tag W. side cor. fence post	S00°W 33.48'
Nail & KC Remon. tag S. side 40" Oak	N73°W 134.08'
Nail & KC Remon. tag N. side 12" & 15" Basswood	S74°W 61.30'
"X" cut on E. end conc. culvert	N22°E 48.76'
"X" cut on W. end conc. culvert	N21°W 50.05'
On approx. C/L "X" road	



Signed by

*Kirk Breitels*

Date

3/27/97

Surveyor's Michigan License No. 30077

P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/27/97

CHAIRMAN *Larry Hubers*