

**SURVEY & REMONUMENTATION**

MAR 03 1998

KENT COUNTY REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

<u>KENT COUNTY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>9W</u>	<u>I-12</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 APR 29 AM 8:19  
REG. OF DEEDS  
*Lucy St. Paul*

**9763**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Mar. 3, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-12	1830	GLO	Mullett	Set Post
	1980	LCRC #1319	VanLaar	Set Capped Iron
	1981	LCRC #2249	Jonker	Set Kent County Monument
	1994	LCRC #6980	Byl	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 11/7/81 and was recorded per LCRC #2249

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-12 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker from remaining witnesses of LCRC #1319 and information from others.

<u>LCRC #2249</u>		<u>LCRC #6980</u>
Remon. tag 32" Sycamore	S12°E 7.02'	Nail & tag 36" Sycamore S12°E 7.00'
Remon. tag 24" Sycamore	N75°E 57.70'	Nail & tag 27" Sycamore N75°E 57.65'
Remon. tag 24" Oak	N56°W 43.43'	Nail & tag 10" Maple N60°W 38.34'
Remon. tag 8" Ash	S80°W 57.76'	Nail & tag 10" Poplar N20°W 8.65'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12 Standard Kent County Monument

Nail & KC Remon. tag E. side	36" Sycamore	S12°E	6.97'
Nail & KC Remon. tag S. side	27" Sycamore	N75°E	57.65'
Nail & KC Remon. tag NE side	10" Maple	N60°W	38.34'
Nail & KC Remon. tag E. side	10" Poplar	N20°W	8.65'

N-S fence is 15'± West



Signed by *Kirk Breitels* Date 3/27/97

Surveyor's Michigan License No. 30077  
P.A. 345 1990 KENT COUNTY  
PEER APPROVED 3/27/97  
CHAIRMAN *Harry Huber*