

**SURVEY & REMONUMENTATION**

MAR 03 1998

**KENT COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
**KENT COUNTY**

(County)

Located In:

Corner Code #

1. Public Land Survey

T	5N	R	9W	J-6
T		R		
T		R		
T		R		
S	T	R		
S	T	R		
S	T	R		
S	T	R		

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORDS  
97 OCT 14 AM 10:30  
REG. OF DEEDS  
*Luis Bond*  
10052

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kirk Breitels, in a field survey on June 13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- J-6 1830---GLO---Not Set
- Williams & Works---No Information
- Kent Co. Wits.---No Information
- 1976---Survey---Consumers Power Co.---Set Iron at Intersection of 1/4 Lines

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 01/28/97  
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
J-6 Found Consumers Power Iron that is less than 0.1' N. & 1.5' E. from intersection of 1/4 lines. Old fence corner to N-S & E-W is 1.5' ± SE of this Iron. The measurements from the C 1/4 to the various 1/4 corners fit the computed intersection of 1/4 lines better than they do the location of the Iron found. No other information in regards to other surveys using the Iron as it sits.

The Intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-6 Set Standard Kent Co. Monument (Harrison) at the Intersection of 1/4 lines.
- Nail & KC Remon. tag W. side 12" Beech N10°W 21.30'
- Nail & KC Remon. tag S. side 24" Maple S90°W 25.72'
- Nail & KC Remon. tag E. side 12" Beech S25°E 22.41'
- Nail & KC Remon. tag N. side 10" Cherry S75°E 45.47'
- Capped Rod (CP Co.) - East 1.51'
- Fence corner N-S & E-W is 2' S. & 2' E.



Signed by [Signature]  
Surveyor's Michigan License No. 30077

Date 9/24/97