

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>KENT COUNTY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 5N R 9W	J-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

97 OCT 14 AM 10:02

REG. OF DEEDS

[Signature]

10029

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on June 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-7 1830---GLO---Mullett---Set Post
1956---Williams & Works---Found no corner - set Iron in line with N-S fences and C/L of road E-W, Fc. Post N 25.32' Fc. Post S 25.10'
1958---Kent Co. Wit.---Iron
18" Cherry WSW 50.45' Iron Fc. Post S 25.40' Conc. Fc. Post N 25.15'
1996---Survey---Exxel---3/4" Pipe
Nail/cap 14" Walnut SW 37.11' Nail/cap P. Pole S 56.85'
Nail/cap 10" Cherry NNW 29.89' Nail/cap Elm NE 69.85'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-7 Found 3/4" Iron Pipe in approx. C/L of E-W asph. road and on fence lines to N-S
Fits witnesses:
Face of Iron Fc. Post S 25.40' Face of Conc. Fc. Post N 25.10'
Fd. Nail/Exxel cap 16" Walnut SE 37.11' Fd. Nail/Exxel cap P. Pole S 56.88'
Fd. Nail/Exxel cap 12" Cherry NNW 29.89' Fd. Nail/Exxel cap 14" Elm NE 69.82'

Iron is less than 0.1' off straight line between NE & NW cor. Sec. 23


The 3/4" Iron Pipe is accepted by me and is generally accepted by professional surveyors as the best available evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-7 Set Standard Kent Co. Monument (Harrison) in place of the 3/4" Iron Pipe

Face of Iron Fence Post	South	25.40'
Face of Conc. Fc. Post	North	25.10'
Nail w/Exxel cap NE side 16" Walnut	S25°E	37.11'
Nail w/Exxel cap W. side P. Pole	South	56.88'
Nail w/Exxel cap SW side 12" Cherry	N10°W	29.89'
Nail w/Exxel cap NW side 14" Elm	N70°E	69.82'

In C/L E-W asph. road ±.
In line of fences N & S ±.



Signed by *[Signature]*
Surveyor's Michigan License No. 30077

Date 8/28/97

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/26/97
CHAIRMAN *[Signature]*