

**SURVEY & REMONUMENTATION**

MAR 03 1998

**KENT COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey	T	5N	R	9W	K-1
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 APR 29 AM 8:19  
REG. OF DEEDS  
9770  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 16, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-1	1830	GLO	Mullett	Set Post
	1936	Kent Co. Wit.		Mon. Box
	1981	LCRC #1625	Byl	Pinched Pipe in Mon. Box
	1985	LCRC #4106	Jonker	Set Kent County Monument in Mon. Box
	1990	LCRC #5465	Starr	Kent County Monument in Mon. Box

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 1/25/85 and was recorded per LCRC #4106

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker on Twp. line in place of the Pinched Pipe inside a Conc. Mon. he found inside a Mon. Box. Said Pipe in Conc. Mon. checks with Kent Co. Wit. and LCRC #1625.  
LCRC #4106  
Remon. tag 20" Maple S30°W 79.04' Nail & tag 20" Maple S30°W 79.04'  
Remon. tag P. Pole N60°W 56.5' Nail & tag P. Pole N60°W 56.50'  
Spike in P. Pole S60°W 61.08' Nail & tag P. Pole S60°W 61.08'  
Kent Co. Mon. East 8.58' C/L stop sign post N70°E 53.00'  
C/L stop sign post N70°E 53' Nail & tag wood post S65°E 53.17'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 Standard Kent County Monument in Mon. Box

Nail & KC Remon. tag SE side 26" Maple	S30°W	78.97'
Nail & KC Remon. tag N. side P. Pole	N60°W	56.54'
Nail & KC Remon. tag NW side P. Pole	S60°W	61.08'
Nail & KC Remon. tag N. side wood post	S65°E	53.22' (post leaning)
C/L stop sign post	N70°E	53.00'
Kent Co. Mon. (K-13, T6N, R9W)	East	8.58'
C/L N-S blacktop pavement is East 4'±		

Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 3/27/97



P.A. 345 1990 KENT COUNTY  
PEER APPROVED 3/27/97  
CHAIRMAN [Signature]