

**SURVEY & REMONUMENTATION**

MAR 03 1998

KENT COUNTY REMONUMENTATION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in  
KENT COUNTY  
(County)

Located In:	Corner Code #
T 5N R 9W	K-8
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Feb. 7, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
97 APR 29 AM 8:20  
REG. OF DEEDS  
*Luis Bond*  
**9776**  
Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-8	1830	GLO	Mullett	Set Post
		Kent Co. Wit.		Fence Post in concrete
1979		LCRC #1270	Bonnema	2" Steel Post in concrete
1981		LCRC #2253	Jonker	Set Kent County Monument cap in concrete
1994		LCRC #6990	Byl	Kent County Monument cap in concrete

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 11/7/81 and was recorded per LCRC #2253

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 Found standard Kent Co. Mon. cap in concrete per witnesses from above LCRC as set by Robert J. Jonker over top of the 2" Steel Post he found in a concrete slab. Said Steel Post checks with Kent Co. Wit. and LCRC #1270.

<u>LCRC #2253</u>	<u>LCRC #6990</u>
Remon. tag 16" Maple N82°W 56.09'	Nail & tag 20" Maple N82°W 56.16'
Remon. tag 12" Pine N38°W 27.70'	Nail & tag 18" Pine N70°E 37.07'
Remon. tag 14" Pine N70°E 37.08'	Nail & tag 12" Pine N10°E 21.80'
Remon. tag 15" Beech S33°E 64.93'	Nail & tag 24" Ash S00°E 83.85'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-8 Standard Kent County Monument cap in concrete
- Nail & KC Remon. tag N. side 20" Maple N82°W 56.16'
  - Nail & KC Remon. tag NW side 18" Pine N70°E 37.07'
  - Nail & KC Remon. tag W. side 12" Pine N10°E 21.80'
  - Nail & KC Remon. tag SE side 12" Poplar S60°W 26.30'
  - Nail & KC Remon. tag W. side 8" Elm S20°E 2.35'
- On E-W fence and near SE corner Pine grove North of #12 tee of golf course to South



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 3/27/97

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 13/27/97  
CHAIRMAN *Harry Huber*