

**SURVEY & REMONUMENTATION**

MAR 03 1998

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**  
**KENT COUNTY**

(County)

Located In:

Corner Code #

1. Public Land Survey

T 5N	R 9W	K-10
T	R	
T	R	
T	R	
S	T R	
S	T R	
S	T R	
S	T R	

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

REG. OF DEEDS

10031

97 OCT 14 AM 10:02

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on June 5, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-10 1830---GLO---Mullett---Set Post  
 ---Williams & Works---No information  
 ---Kent Co. Wit.---No information  
 1985---LCRC #4273---Bonnema---Found cut off "L" fence post in concrete at intersection of North, East & West fences.  
 24" Maple North 50.20' 10" Maple ENE 36.25'  
 30" Maple SW 16.10' 20" Maple SE 26.96'  
 "T" post North 0.75'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10 Found "L" fence post 3" tall in 2' dia. conc. footing per the following witnesses:  
 C/L Tw. 16" Maple North 50'±  
 C/L 14" Maple ENE 36.3'±  
 C/L 26" Maple SE 27'±  
 "T" post North 0.70'  
 At fences to East and North

The "L" fence post in concrete is accepted by me and is generally accepted by professional surveyors as the best available evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10 "L" fence post, 3" tall, in concrete footing  
 Set Nail & KC Remon. tag E. side Tw. 16" Maple N05°E 50.04'  
 Set Nail & KC Remon. tag S. side 14" Maple N90°E 36.28'  
 Set Nail & KC Remon. tag SW side 26" Maple S35°E 27.07'  
 Set Nail & KC Remon. tag S. side 10" Maple S85°W 31.20'  
 At fences to East and North



Signed by Kirk Breitels  
 Surveyor's Michigan License No. 30077

Date 8/28/97

P.A. 345 1990 KENT COUNTY

PEER APPROVED 6/26/97

CHAIRMAN Harry Hubert

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983  
 REVISED OCT., 1985