

SURVEY & REMONUMENTATION

MAR 03 1998

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY

(County)

Located in:

Corner Code #

- | | | |
|------------------------------------|---|-------------|
| 1. Public Land Survey | T <u>5N</u> R <u>9W</u> | <u>K-12</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

REG. OF DEEDS

Lucy Bond

97 APR 29 AM 8:20

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

9779

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-12	1830	GLO	Mullett	Set Post
		Kent Co. Wit.		C/L RR rail in conc.
	1980	LCRC #1391	Herrema	RR rail in conc.
	1995	LCRC #8755	Jonker	RR rail in conc. (5 1/2' high)

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, verified (no monument set) by Robert J. Jonker on 8/24/95 and was recorded per LCRC #8755.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-12 Found RR rail fence post (5 1/2' high) per witnesses from above LCRC as verified by Robert J. Jonker. Said RR rail checks with Kent Co. Wit. and LCRC #1391.

LCRC #8755

Nail & KC Remon. tag S. side	32" Beech	S85°E	43.3'
Nail & KC Remon. tag N. side	33" Maple	N85°W	30.7'
Nail & KC Remon. tag W. isde	18" Cherry	S05°W	40.5'
Nail & KC Remon. tag NW side	8" Ash	S45°W	45.2'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 RR rail fence post (5 1/2' tall)			
Nail & KC Remon. tag S. side	32" Beech	S85°E	43.3'
Nail & KC Remon. tag N. side	33" Maple	N85°W	30.7'
Nail & KC Remon. tag W. isde	18" Cherry	S05°W	40.5'
Nail & KC Remon. tag NW side	8" Ash	S45°W	45.2'



Signed by *Kirk Breitels*

Date 3/27/97

Surveyor's Michigan License No. 30077
P.A. 345 1990 KENT COUNTY

PEER APPROVED 3/27/97
CHAIRMAN *Stan Kuberski*